No.	Items	Per	Quantity
29	Steel ferrot drain cleaner $1\frac{1}{2}$" diameter of 3' long	No.	2
30	Do 1" do	"	2
31	Do $\frac{3}{4}$" do	"	2
32	Do $\frac{1}{2}$" do	"	2
33	Do $\frac{1}{8}$" do	"	2
	(3) *Constructing underground combined latrine and urinals.*		
1	Doulton's white queensware large area closet with paisely cistern polished brass pipe No. 837 as per Doulton's Catalogue.	Each	1
2	Doulton's Improved Hindustani closet. Page No. 333 as per Richardson and Cruddas Catalogue on Sanitary fittings.	"	2
3	Doulton's single person circular backed urinals, etc., No. 739, page 344, as per Doulton's Catalogue.	"	4
4	4" cast iron bends of 100 degrees	"	1
5	Do soil pipe	R. ft.	30
6	4"×4" cast iron single junction pipe 100 degrees	Each	1
	(4) *Laying stoneware pipes outside connections up to Sampige tank.*		
1	7" stoneware pipes	R. ft.	6,430
2	Cast iron manwhole cover and frame	Each	37
3	Do steps	"	74
4	Field flushing apparatus 4" diameter	"	4
5	4"×4" stone sewer trap	"	8
6	Wrought iron ventilating shaft 4" diameter 20' length	"	1

N. SUBBA RAO,
Offg. Executive Engineer.

MYSORE DIVISION.

Notice.

The attention of the public is invited to advertisement in detail published in *Mysore Gazette*, dated 25th April 1918, calling for tenders for constructing Village Elementary Boys' School at Haradanahalli in Chamrajnagar Taluk.

P. SUBBA RAO,
For *Executive Engineer.*

KOLAR DIVISION.

Dated 27th April 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 16th May 1918, for extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

960

Approximate estimate of quantities for extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation and filling the earth to basement level including consolidation.	C. yd.	193
2	Concrete in mortar	C. ft.	1,949
3	Burnt stone in chunam including bond stones	"	4,753
4	Burnt brick in chunam	"	6,903
5	Plastering with lime mortar	Sqr.	97·50
6	Pointing with lime mortar	"	5·12
7	White and colorwashing two coats	"	102·60
8	Burnt stone slabs dressed	S. ft.	1,035
9	Providing bond stones	Each	16
10	Cut stone pillars with basis and capitals including dressing	"	12
11	Teakwood work wrought and put up	C. ft.	335·4
12	Teakwood finials	Each	6
13	Teakwood pendant	"	12
14	Teakwood ornamental eave board 9" wide	R. ft.	408
15	Wood oiling	Sqr.	30
16	Roofing with 1st class Mangalore tiles on teak reepers 2"×1" with wood-oiling to reepers, etc., complete.	"	44·35
17	Mangalore ridge tiles set in mortar	R. ft.	174
18	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing	Sqr.	14·03
19	Teakwood railing with painting as shown in plan	R. ft.	99
20	Teakwood doors panelled with iron hold fasts frames and double teakwood shutters with bolts, hinges, lock and key, etc., complete.	S. ft.	336
21	Teakwood windows ½ glazed and ½ panelled shutters fixed outside with iron hold fasts, hinges, hooks and rings and iron bars, etc., complete	"	306
22	Teakwood glazed circular ventilators	"	28·28
23	Teakwood shelves with frames, shutters, etc., complete with lock and key	"	132
24	Providing dormer windows with glazed shutters and necessary masonry work and removing the existing roof and complete.	Each	4
25	Chocolate painting two coats	Sqr.	18·4
26	Providing teakwood screen wall as a panelled pattern with necessary door arrangements and iron fittings and painting complete.	S. ft.	565
27	Providing zinc gutters with 3" width sheet and borders on either side including planking ½" thick arrangements under gutters.	"	444

V. V. KARVE,
Executive Engineer.

CHITALDRUG DIVISION.

The attention of the contracting firms is invited to page 359, Part IV of the *Mysore Gazette* of April 25th, 1918, calling for tenders for supply of "Roofing and Flooring materials," for use in the Division.

Tenders will be received up to 10th May 1918.

Approved competitor will be informed by the 15th May 1918 and the supply should be completed by the 15th June 1918.

For other particulars see page of Gazette quoted above.

N. ANANDALWAR,
Executive Engineer.

DISTRICT, MUNICIPAL AND LOCAL BOARDS.

BANGALORE CITY MUNICIPALITY.

Notice dated 29th April 1918.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated the 25th April 1918, Part IV, page 362, calling for tenders for constructing two rows of sweepers' quarters on the Mysore road. The latest date for submitting tenders is 3rd May 1918.

Notice dated 29th April 1918.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated the 25th April 1918, Part IV, page 362, calling for tenders for building a combined vegetable and mutton market, etc., in Huriopet. The latest date for submitting tenders is 10th May 1918.